

**MT. SAN JACINTO COMMUNITY COLLEGE  
DISTRICT**

**ADDENDUM NO. 4**

**Bid 2022-002  
Parking Lots D & E Resurfacing at  
San Jacinto Campus**

**December 2, 2021**

**Owner:  
Mt. San Jacinto Community College District  
1499 No. State Street  
San Jacinto, California 92583**

**RECEIPT OF THIS ADDENDUM MUST BE ACKNOWLEDGED ON BID  
FORM WHEN SUBMITTED**

## **ADDENDUM NO. 4**

### **Bid 2022-002 Parking Lots D & E Resurfacing at San Jacinto Campus**

The following changes, additions, deletions or corrections shall become a part of the Contract Documents for the project named above and all other conditions shall remain the same. The bidders shall be responsible for transmitting this information to all affected subcontractors and suppliers prior to the closing of bids. Prospective Bidders shall acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject Bidder to disqualification.

Questions and Answers

#### **Item No. AD-4-1:**

- Q. Under Paint: You are asking for thermoplastic paint. This is not what you have onsite and it is extremely expensive. Are you sure that this is what you are looking for? Also, if we have to paint bollards or curbs you cannot use this product. Please clarify.
- A. Thermoplastic paint where applicable due to its longevity and high traffic area in the Maintenance/corp yard. Curbs and other bollards can be a contractor supplied approved substitute.

#### **Item No. AD-4-2:**

- Q. Under Pavement: you mention aggregate base but none is to be done as part of the revised scope of work. You also mention Type B Asphalt for final lift and 3/4" Asphalt for lower lifts. Since we are paving 4" do you want 2" and 2" of each product?
- A. Yes, this is a minimum requirement not a limitation.

#### **Item No. AD-4-3:**

- Q. Under Crack Seal/Joint Seal: You provide specs but since all the asphalt in the revised scope of work is a full removal and replacement this spec seems unnecessary. Please clarify?
- A. All joints will be crack sealed as stated in specification, along concrete edges, around left/existing asphalt etc.

**Item No. AD-4-4:**

- Q. Under Asphalt Seal Coat: You mention 2 coats of seal. The scope of work does not mention sealcoating. Do you want the new pavement sealed and if so you must realize that you cannot place thermoplastic paint and then place sealcoat over the top. Thermoplastic paint must be ground off before you can place sealcoat. Please clarify your intent.
- A. Asphalt should be to industry standards which requires sealcoating, contractor to create a timeline to best suit the project, but in regard to the thermoplastic paint for striping purposes it will have to be after the cure time and after the sealcoat

**This is the end of Addendum No. 4**